



"Quality & Service are the Roots of our Business"

September 30th, 2015

Ben Franklin School
Menomonee Falls WI

Poured in place surfacing:

We will remove the mulch around the new playground for the 4K students. The area is approximately 40 by 50 feet. We will install a gravel base and PIP surfacing. The surfacing will be 2" total depth – 1 ½" base and ½" top with a 50% black and 50% color top. The PIP surfacing will butt up to the asphalt on 2 sides and will roll down into the mulch on the two sides that are next to the other play equipment. Work will be done in spring of 2016.

Total price all labor and material \$ 26,100.00

We will remove and dispose of the mulch around the main structure and the climbing bars on the north side of the playground. The area is approximately 75 by 42 feet. We will install a gravel base and PIP surfacing. The surfacing will be 3" total depth – 2 ½" base and ½" top with a 50% black and 50% color top. The PIP surfacing will butt up to the asphalt on 2 sides and will roll down into the grass on the east and the mulch of the rest of the play equipment on the south side. Work will be done in spring of 2016.

Total price all labor and material \$ 44,100.00

Reduce this area to not include the areas next to the asphalt and on the back side next to the grass so as to not include the climbing bars, so that we only surface the play areas and not the open areas. The surfacing will then roll down into the mulch on all 4 sides and the children will transfer from the asphalt to wood chips and then to surfacing. By doing this we are reducing the area that needs to be surfaced to 2000 sq. ft.

Total price all labor and material \$ 31,450.00

Thank you for the opportunity, any questions my cell is 414-305-8875.

Michael Bluemel